

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

\$7.00
\$2.00

MAR 08 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

98 JUL 14 AM 9:54

SECTION

For corners in
KENT COUNTY

(County)	Located In:	Corner Code #
1. Public Land Survey	T ^{9N} R ^{11W}	G-4
	T_____ R_____	_____
	T_____ R_____	_____
	T_____ R_____	_____
2. Property Controlling in Section	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____
3. Miscellaneous Property in Sec.	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____

Luigi Bond
REG. OF DEEDS

10648

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on June 22, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9	●	10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-4	1837	GLO	Whitcomb	Set Post
	1895	Williams & Works		Stone
	1955	Williams & Works		Iron
		Kent Co. Wits		Boat Spike
	1966	Williams & Works		Mon. Box
	1983	LCRC #3670	Bueche	Set Kent County Monument in Mon. Box
	1990	LCRC #5682	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/25/98
CHAIRMAN Harry Bueche

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 12-12-83 and was recorded per LCRC #3670.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-4 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 3/4" Iron he found inside a Mon. Box. Said Iron checks with Williams & Works and Kent Co. Wits.

LCRC #3670	LCRC #5682
Nail & Remon. tag P. Pole N75°E 31.05'	NE cor. hse. fnd. S70°W 109.03'
Nail & Remon. tag 10" Elm S50°E 34.99'	Nail & Remon. tag fc. post West 34.56'
Nail & Remon. tag Fc. Post N90°W 34.31'	Nail & Remon. tag 6" Maple S25°E 76.46'
Nail in side dbl. 12" Maple S25°E 78.23'	Nail & Remon. tag P. Pole N75°E 31.07'
NW cor. hse. fnd. S70°W 108.95'	S. end of bridge is North 36' ±

S. end of bridge is North 37' ±

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-4 Standard Kent County Monument in Mon. Box	
NE corner house foundation	S70°W 108.98'
Nail & KC Remon. tag S. side fence corner post	West 34.72' (leaning N.)
Nail & KC Remon. tag E. side 10" Maple	S25°E 76.44'
Nail & KC Remon. tag N. side P. Pole	N75°E 31.07'
Nail & KC Remon. tag top of guard rail post	N20°E 34.50'
Nail & KC Remon. tag top of guard rail post	N20°W 34.22'
South end of bridge is North 36' ±	



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 6/25/98