

MAR 08 1999

\$7.00  
\$2.00

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>9</u> N R <u>11</u> W	G-6
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 28, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-6	1837	GLO	Whitcomb	Set Post
	1959	Kent Co. Wits		1" Iron
	1978	LCRC #1243	Merdzinski	5/8" Iron in Mon. Box
	1981	LCRC #2468	Jonker	Set Kent County Monument in Mon. Box
	1990	LCRC #5684	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/19/98  
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 11-20-81 and was recorded per LCRC #2468.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

G-6 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 5/8" Iron he found inside a Mon. Box. Said Iron checks checks with Kent Co. Wits. and LCRC #1243.

LCRC #2468	LCRC #5684
Nail & Remon. tag 8" Pine S49°W 32.30'	Chiseled "X" in top E. end conc. culv. S65°E 36.39'
Nail & Remon. tag 6" Pine N54°W 24.40'	Chiseled "X" in top W. end conc. culv. S71°W 44.42'
Nail & Remon. tag 14" Ash N89°E 94.97'	Nail & Remon. tag 8" Pine S53°W 25.44'
PK Nail in top of guard post S55°E 35.70'	Nail & Remon. tag 16" Ash N86°E 94.99'
PK Nail in top of fence post S88°E 33.24'	

On fence line East & fence to West is 6' North

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6 Standard Kent County Monument in Mon. Box	
"X" cut in top of E. end concrete culvert	S65°E 36.39'
"X" cut in top of W. end concrete culvert	S71°W 44.42'
Nail & KC Remon. tag S. side (7' high) P. Pole	N75°E 50.20'
Nail & KC Remon. tag NE side (5' high) 12" Pine	N35°W 50.88'
C/L N-S pavement is 1' West	

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
98 MAR -5 AM 8:33  
REG. OF DEEDS  
[Signature]

10535  
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 2/19/98