

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T 9N	R 11W	G-8
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

98 MAR -5 AM 8:33

REG. OF DEEDS

W. J. Rosema

10537

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-8	1837	GLO	Whitcomb	Set Post
	1962	Kent Co. Wits		3/4" Iron
	1983	LCRC #3450	Jonker	3/4" Iron in Mon. Box
	1985	LCRC #4336	Rosema	Set Kent County Monument
	1990	LCRC #5686	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Maurice J. Rosema on 12-16-85 and was recorded per LCRC #4336.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-8 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Maurice J. Rosema in place of the 3/4" Iron he found inside a Mon. box. Said Iron checks with Kent Co. Wits. and LCRC #3450.

LCRC #4336		LCRC #5686
Chiseled "X" on E. end culv.	N36°E 58.67'	Nail & Remon. tag P. Pole N24°W 106.86'
Nail & Remon. tag 18" Oak	S60°E 79.45'	Chiseled "X" on E. end conc. culv. N32°E 58.68'
Nail & Remon. tag 12" Box Elder	S29°E 98.24'	Nail & Remon. tag 20" Oak S64°E 79.44'
Nail & Remon. tag 6" Elm clump	S78°W 95.43'	Nail & Remon. tag 18" Poplar S32°E 98.25'
Nail & Remon. tag P. Pole	N20°W 106.93'	On C/L "X" of roads N-S & E-W

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8 Standard Kent County Monument

Nail & KC Remon. tag NE side P. Pole	N24°W	106.86'
"X" cut on E. end of concrete culvert	N32°E	58.68'
Nail & KC Remon. tag S. side 22" Oak	S64°E	79.44'
Nail & KC Remon. tag SW side 20" Poplar	S32°E	98.28'
On C/L roads N-S & E-W ±		



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/19/98