

\$7.00  
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

KENT COUNTY  
(County)

Located in: Corner Code #

- 1. Public Land Survey T 9N R 11W G-10  
T R  
T R  
T R
- 2. Property Controlling in Section S T R  
S T R
- 3. Miscellaneous Property in Sec. S T R  
S T R
- 4. Lot No. , Recorded Plat
- 5. Private Claims

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
98 MAY 21 AM 8:31  
REG. OF DEEDS  
*David J. Bond*

10610

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on April 7, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-10 1837 GLO	Whitcomb	Set Post
1962 Kent Co. Wits		Mon. Box
1972 LCRC #358	Spicer	1" Iron in Mon. Box
1972 LCRC #457	VanKooten	Iron in Mon. Box
1977 LCRC #1079	McCloskey	3/4" Iron in Mon. Box
1982 LCRC #2519	Starr	Set Kent County Monument in Mon. Box
1990 LCRC #5688	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 4/30/98  
CHAIRMAN *Henry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas C. Starr on 1-5-82 and was recorded per LCRC #2519.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-10 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Thomas C. Starr in place of the 3/4" Iron Pipe he found inside a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC's #358, #457, #1079, LCRC #2519 LCRC #5688

Nail & Remon. tag 24" Ash S70°W	87.95'	Nail & Remon. tag P. Pole N79°W	118.78'
Nail & Remon. tag P. Pole N70°W	118.85'	Nail & Remon. tag 26" Ash S73°W	87.85'
Nail & Remon. tag 12" Elm S50°E	49.21'	Nail & Remon. tag 28" Elm S53°E	48.93'
Nail & Remon. tag P. Pole S85°E	31.39'	Nail & Remon. tag P. Pole S87°E	31.32'
Nail & Remon. tag 8" Elm N55°E	53.17'	Nail & Remon. tag 10" Elm N48°E	53.32'

"X" on curb S45°W 36.17' "X" on curb N45°W 35.94' "X" on curb N47°W 35.95' "X" on curb S45°W 36.18'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10 Standard Kent County Monument

Nail & KC Remon. tag S. side P. Pole	N79°W	118.78'
Nail & KC Remon. tag N. side 30" Ash	S73°W	87.88'
Nail & KC Remon. tag N. side 30" Elm	S53°E	48.72'
Nail & KC Remon. tag N. side P. Pole	S87°E	31.46'
"X" cut on top of curb	N47°W	35.95'
"X" cut on top of curb	S45°W	36.18'

On C/L roads N-S-W



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 4/30/98