

~~\$7.00~~
\$2.00

KENT COUNTY REMONUMENTATION MAINTENANCE

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T 9N R 11W

G-13

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____

T _____ R _____

S _____

T _____ R _____

3. Miscellaneous
Property in Sec.

S _____

T _____ R _____

S _____

T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kirk Breitels, in a field survey on Oct. 28, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-13 Kent County Monument, LCRC #9134, 3/1/96
Nail & KC Remon. tag E. side P. Pole S00°W 121.17'
Top of South corner of conc. ROW marker N20°W 97.28'
Top of South corner of conc. ROW marker N16°E 121.50'
2" Angle Iron fence corner post N50°E 117.40'
Kent Co. Mon. (G-1, T8N, R11W) East 338.70'

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/1/99
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13 Found BROKEN Kent Co. Monument per all of the above witnesses. Removed and reset Kent Co. Monument

SURVEY & REMONUMENTATION

MAR 08 1999

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 Standard Kent County Monument
Nail & KC Remon. tag E. side P. Pole S00°W 121.13'
Top of South corner of conc. ROW marker N20°W 97.28'
Top of South corner of conc. ROW marker N16°E 121.50'
2" Angle Iron Fence Corner Post N50°E 117.40'
Kent Co. Mon. (G-1, T8N, R11W) East 338.70'



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 12/15/98

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 DEC 23 AM 8:59
REG. OF DEEDS
[Signature]
11077
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	18			17			16			15			14	13
7														
8	19			20			21			22			23	24
9														
10	30			29			28			27			26	25
11														
12	31			32			33			34			35	36
13														