

MAR 08 1999

KENT COUNTY REMONUMENTATION

\$7.00  
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY  
(County)

Located in:

Corner Code #

- 1. Public Land Survey      T 9N R 11W      H-5
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling      S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section                    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec.            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 19, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- H-5 1837 GLO Whitcomb Set Post
- 1956 Kent Co. Wits Iron
- 1978 LCRC #1243 Merdzinski "T" Iron
- 1983 LCRC #3487 Bueche Set Kent County Monument
- 1994 LCRC #7018 Byl Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 6-27-83 and was recorded per LCRC #3487.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-5 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the "1" Iron he found over a 2<sup>nd</sup> "T" Iron. Both "T" Irons check with LCRC #1243.

LCRC #3487	LCRC #7018
Nail & Remon. tag P. & Pole N60°W 64.00'	Nail & Remon. tag P. & T. Pole N60°W 63.95'
Nail & Remon. tag 8" Pine S70°W 63.20'	Nail & Remon. tag 10" Pine S70°W 63.14'
Nail & Remon. tag 12" Pine S15°E 33.90'	Nail & Remon. tag 14" Pine S15°E 33.66'
Nail & Remon. tag 10" Pine S50°E 56.28'	Nail & Remon. tag 12" Pine S50°E 56.32'
SW cor. Hse. #2809 N10°E 81.71'	Nail & Remon. tag P. Pole S10°W 98.01'
Mon. Box - West 14.6'	SW cor. Hse. #2809 N10°E 81.71'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-5 Standard Kent County Monument
- Nail & KC Remon. tag N. side P. & T. Pole N60°W 63.95'
- Nail & KC Remon. tag NW side 12" Pine S70°W 63.14'
- Nail & KC Remon. tag W. side 16" Pine S15°E 33.66'
- Nail & KC Remon. tag NE side 14" Pine S50°E 56.29'
- Nail & KC Remon. tag E. side P. Pole S10°W 98.01'
- SW corner House #2809 N10°E 81.71'
- C/L drive to S. is W. 10' - Fence N. is W. 21.6' ±
- On C/L E-W blacktop road



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 2/19/98

REG. OF DEEDS  
*Luigi Standa*  
98 MAR -5 AM 8:33  
STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

10540  
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/19/98  
CHAIRMAN *John C. Bueche*