

MAR 08 1999

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$7.00
\$2.00

SECTION

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 9N R 11W H-7
- T _____ R _____
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
- S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
- S _____ T _____ R _____

REG. OF DEEDS

Luci Standa

98 MAR -5 AM 8:33

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

10541

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 19, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- H-7 1837 GLO Whitcomb Set Post
- 1970 Kent Co. Wits Mon. Box
- 1975 LCRC #883 Nederveld 3/4" Iron in Mon. Box
- 1982 LCRC #2516 Starr Set Kent County Monument in Mon. Box
- 1994 LCRC #7019 Byl Kent County Monument in Mon. Box

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/19/98

CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas C. Starr on 1-5-82 and was recorded per LCRC #2516.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Thomas C. Starr in place of the 1/2" Iron Pipe he found inside a Mon. Box. Said 1/2" Iron in Mon. Box checks with Kent Co. Wits. and LCRC #883.

LCRC #2516

LCRC #7019

- | | |
|--|---|
| Nail & Remon. tag 4" Poplar S45°E 73.80' | Nail & Remon. tag Tri. 16" Oak S00°E 68.84' |
| Nail & Remon. tag 14" Oak South 68.84' | Nail & Remon. tag 8" Cedar S20°W 85.16' |
| Nail & Remon. tag 4" Cedar S20°W 85.07' | Nail & Remon. tag 12" Pine N50°W 73.34' |
| Nail & Remon. tag 8" Pine N50°W 73.67' | Nail & Remon. tag 15" Pine N20°E 143.73' |
| Nail & Remon. tag 10" Pine N20°E 143.76' | Nail & Remon. tag P.Pole N00°E 41.90' |
| Nail & Remon. tag P. Pole N40°W 89.77' | Nail & Remon. tag 6" Poplar S45°E 79.41' |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 Standard Kent County Monument in Mon. Box

- Nail & KC Remon. tag W. side Tri. 18" Oak S00°E 68.75'
- Nail & KC Remon. tag NW side 10" Cedar S20°W 85.16'
- Nail & KC Remon. tag S. side 16" Pine N50°W 73.24'
- Nail & KC Remon. tag W. side 16" Pine N20°E 143.73'
- Nail & KC Remon. tag E. side P. Pole N00°E 41.90'
- Nail & KC Remon. tag NE side 8" Poplar S45°E 79.41'
- On tree row S. and C/L dirt drive N.



Signed by Kirk Breitels

Date 2/19/98

Surveyor's Michigan License No. 30077