

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY  
(County)

Located In:

Corner Code #

- |                                    |              |               |              |
|------------------------------------|--------------|---------------|--------------|
| 1. Public Land Survey              | T <u>9</u> N | R <u>11</u> W | H-8          |
|                                    | T <u>   </u> | R <u>   </u>  | <u>   </u>   |
|                                    | T <u>   </u> | R <u>   </u>  | <u>   </u>   |
|                                    | T <u>   </u> | R <u>   </u>  | <u>   </u>   |
| 2. Property Controlling in Section | S <u>   </u> | T <u>   </u>  | R <u>   </u> |
|                                    | S <u>   </u> | T <u>   </u>  | R <u>   </u> |
| 3. Miscellaneous Property in Sec.  | S <u>   </u> | T <u>   </u>  | R <u>   </u> |
|                                    | S <u>   </u> | T <u>   </u>  | R <u>   </u> |

REG. OF DEEDS

*Handwritten signature*

38 OCT -7 AM 10:15

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

10685

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Aug. 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- |          |                      |  |
|----------|----------------------|--|
| H-8 1837 | GLO                  | Not Set  |
| 1953     | Kent Co. Wits        | Iron as set by Donker  |
| 1954     | Williams & Works     | Set Boat Spike on true N-S 1/4 line and E-W fence line   |
| 1964-73  | Williams & Works     | Set/Used "T" Iron at true center (old position 7.55' South and Iron by Donker is 6.9' N. & 11.3' W.) |
| 1973     | LCRC #534 Spicer     | "T" Iron   |
|          | Fe. Post N89°E 21.85 | 32" Oak S85°E 217.95' Fe. Line N 2.5' C/L rd. W ??? N. leg sign S 3.1'                               |

P.A. 345 1990 KENT COUNTY

PEER APPROVED 9/24/98  
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- H-8 Found "T" Iron per the following remaining witnesses:  
C/L 40" Oak S85°E 218' ± Old sign post S 3' ±

Said "T" Iron is 0.0' W. and 0.1' S. of Intersection of 1/4 lines and has been used in survey by Williams & Works and Ed Glaza

The "T" Iron is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-8 Set Standard Kent County Monument in place of the "T" Iron
- |                                      |       |         |
|--------------------------------------|-------|---------|
| Nail & KC Remon. tag S. side 40" Oak | S85°E | 217.74' |
| Nail & KC Remon. tag E. side P. Pole | S10°W | 224.65' |
| Nail & KC Remon. tag N. side P. Pole | S85°W | 350.58' |
| N. edge sign post leg                | S70°W | 69.93'  |
| S. edge of S. sign post leg          | N05°W | 2.67'   |
- C/L of N-S gravel road is 18' ± West.



Signed by [Signature]  
Surveyor's Michigan License No. 30077

Date 9/25/98