

**SURVEY & REMONUMENTATION**

MAR 08 1999

**KENT COUNTY REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located in:

Corner Code #

- |                                    |                            |             |
|------------------------------------|----------------------------|-------------|
| 1. Public Land Survey              | T <u>9</u> N R <u>11</u> W | <u>H-10</u> |
|                                    | T _____ R _____            | _____       |
|                                    | T _____ R _____            | _____       |
|                                    | T _____ R _____            | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____    | _____       |
|                                    | S _____ T _____ R _____    | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____    | _____       |
|                                    | S _____ T _____ R _____    | _____       |

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 98 OCT -7 AM 10:15  
 REG. OF DEEDS  
*W. J. Bond*

**10686**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Aug. 4, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-10 1837 GLO Not Set  
 1976 Williams & Works Surveys indicate Intersection of 1/4 lines  
 Kent Co. Wits (does not show setting anything at corner)  
 No information

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 8/20/98  
 CHAIRMAN *Harry Fisher*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-10 Established Intersection of 1/4 lines and found nothing at corner.

Remains of fences: West is 4' South - South is 4' West - On line to East  
 Corner fall in dirt "foot path" running Easterly-Westerly through woods.

Measurements agree with 1976 Williams & Works survey ± and computations of other's in this Section.

The Intersection of 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-10 Set Standard Kent County Monument at Intersection of 1/4 lines  
 Nail & KC Remon. tag W. side 18" Maple N15°E 10.62'  
 Nail & KC Remon. tag N. side 6" Maple S85°W 17.32'  
 Nail & KC Remon. tag E. side 30" Maple South 9.88'  
 Nail & KC Remon. tag E. side 20" Oak S20°E 31.45'  
 Nail & KC Remon. tag N. side 20" Maple East 41.82'  
 On old fence line to East, old fence to West is 4' South, old fence to South is 4' West



Signed by *Kirk Breitels*  
 Surveyor's Michigan License No. 30077

Date 9/29/98