

FEB 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
98 MAR -5 AM 8:33  
REG. OF DEEDS  
*Lucy Stord*

For corners in

KENT COUNTY  
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 9N R 11W H-11
- T R
- T R
- T R
- T R
- 2. Property Controlling in Section S T R
- S T R
- 3. Miscellaneous Property in Sec. S T R
- S T R

10543

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Kirk Breitels, in a field survey on Jan. 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- H-11 1837 GLO Whitcomb Set Post
- 1967 Kent Co. Wits Mon. Box
- 1972 LCRC #457 VanKooten Mon. Box
- 1982 LCRC #2523 Starr Set Kent County Monument
- 1994 LCRC #7021 Byl Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/19/98  
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas C. Starr on 1-5-82 and was recorded per LCRC #2523.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-11 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Thomas C. Starr inside a Mon. Box (No Iron inside) he found. Said Mon. Box checks with Kent Co. Wits. and LCRC #457.

LCRC #2523	Nail & Remon. tag P. Pole	S15°W	89.43'	LCRC #7021	Nail & Remon. tag P. Pole	S15°W	89.38'
	Nail & Remon. tag 6" Maple	S40°W	84.60'		Nail & Remon. tag 10" Maple	S40°W	84.65'
	Nail & Remon. tag 10" Maple	S60°W	101.87'		Nail & Remon. tag 12" Maple	S60°W	101.95'
	Nail & Remon. tag 8" Maple	N10°W	49.90'		Nail & Remon. tag 12" Maple	N10°W	49.90'
	Nail & Remon. tag 10" Maple	N20°E	55.00'		Nail & Remon. tag 12" Maple	N20°E	55.03'

C/L E-W road is S. 8.5' and on tree row N.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-11 Standard Kent County Monument in Mon. Box
- Nail & KC Remon. tag W. side P. Pole S15°W 89.38'
- Nail & KC Remon. tag NW side 12" Maple S40°W 84.65'
- Nail & KC Remon. tag NW side 14" Maple S60°W 101.95'
- Nail & KC Remon. tag E. side 16" Maple N10°W 49.83'
- Nail & KC Remon. tag W. side 18" Maple N20°E 54.95'
- C/L E-W road is S. 8.5' ± and on tree row to N.



Signed by [Signature]  
Surveyor's Michigan License No. 30077

Date 2/19/98