

FEB 14 1997

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 9N R 11W H-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number
9135
96 MAR 20 AM 9:00
STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

- 4. Lot No. Recorded Plat
5. Private Claims

I, Kirk Breitels, in a field survey on Jan. 25, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked at row 13, column H.

A. Description of original monument and accessories and/or subsequent restoration:

H-13 1837 GLO Brookfield Set Post
Kent Co. Wit. Mon. Box
1979 LCRC #1269 Bonnema 3/4" Iron Im Mon. Box
1981 LCRC #1756 Merdzinski Set Kent County Monument
1994 LCRC #7022 Byl Kent County Monument

P.A. 345 1990 KENT COUNTY,

PEER APPROVED 3/7/96
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 1/15/81 and was recorded per LCRC #1756

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 3/4" Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wit. and LCRC #1269

LCRC #1756 LCRC #7022
Nail/Tag 4" Locust S35°W 68.18' Nail/tag 8" Locust S35°W 67.96'
Nail/Tag P. Pole N70°W 162.87' Nail/tag G. Post S80°E 97.73'
Nail/Tag Fc. Post N00°E 51.11' Nail/tag P. Pole N00°E 42.20'
Nail/Tag G. Post S80°E 103.18' Nail/tag P. Pole N80°W 185.00'
C/L Mon. box East 251.39' Kent Co. Mon. S90°E 251.36'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 Standard Kent County Monument
Nail & KC Remon. tag NW side 10" Locust S35°W 67.96'
Nail & KC Remon. tag top of guard rail post S80°E 97.73'
Nail & KC Remon. tag E. side P. Pole N00°E 42.20'
Nail & KC Remon. tag S. side P. Pole N80°W 185.00'
Kent Co. Mon. (H-1, T8N, R11W) S90°E 251.38'



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 3/2/96