

SURVEY & REMONUMENTATION

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located in:

Corner Code #

1. Public Land Survey

T 9N R 11W I-4
T R
T R
T R
S T R
S T R
S T R
S T R

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-4 1837 GLO Whitcomb Set Post
- 1966 Kent Co. Wits Iron
- 1981 LCRC #1620 Hackbardt 1/2" Rod
- 1982 LCRC #2881 Jonker Set Kent County Monument
- 1994 LCRC #7025 Byl Reset Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 5-27-82 and was recorded per LCRC #2881.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-4 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by William R. Byl in the same location as set in 1982 by Robert J. Jonker in place of the 1/2" Rod with stake and stones underneath he found. All check with Kent Co. Wits. and LCRC #1620.

LCRC #2881	LCRC #7025
Nail & Remon. tag 16" Spruce S55°W 57.46'	Nail & Remon. tag 20" Spruce S55°W 57.15'
Nail & Remon. tag 18" Oak N50°E 39.25'	Nail & Remon. tag 24" Oak N50°E 39.25'
Nail & Remon. tag P. Pole S50°E 33.73'	Nail & Remon. tag P. Pole S50°E 33.73'
Nail & Remon. tag P. Pole N60°W 66.6'	Nail & Remon. tag P. Pole N60°W 66.61'

On tree row W. and fence line E.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-4 Standard Kent County Monument
- Nail & KC Remon. tag SE side 20" Spruce S55°W 57.15'
- Nail & KC Remon. tag SE side 24" Oak N50°E 39.20'
- Nail & KC Remon. tag SW side P. Pole S50°E 33.73'
- Nail & MSHD tag SW side P. Pole N60°W 66.61'



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 2/19/98

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:33
REG. OF DEEDS
Lucy Storch
10546
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													