

MAR 08 1999

KENT COUNTY REMONUMENTATION

\$7.00
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located In:	Corner Code #
T 9N R 11W	I-6
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-6	1837 GLO	Whitcomb	Set Post
	1980 LCRC #1358	Merdzinski	Found remains of wood post - Set "T" Iron
	1983 LCRC #3805	Bueche	Set Kent County Monument
	1994 LCRC #7027	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 12-29-83 and was recorded per LCRC #3805.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the "T" Iron he found. Said "T" Iron checks with LCRC #1358 and 1 remaining GLO witness.
LCRC #3805

LCRC #3805		LCRC #7027	
Nail & Remon. tag 22" Oak	N40°W 28.95'	Nail & Remon. tag 27" Oak	N40°W 28.96'
Nail & Remon. tag 12" Maple	North 25.73'	Nail & Remon. tag 15" Maple	N00°E 25.70'
Nail & Remon. tag 14" Oak	S60°E 20.32'	Nail & Remon. tag 14" Oak	S60°E 20.40'
Nail & Remon. tag 14" Poplar	S15°E 38.80'	Nail & Remon. tag 14" Poplar	S15°E 39.05'
Cut Nail in 12" Oak	S15°E 6.00'	Nail & Remon. tag 12" Oak	S15°W 5.90'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6 Standard Kent County Monument	
Nail & KC Remon. tag SW side 27" Maple	N40°W 28.96'
Nail & KC Remon. tag W. side 15" Maple	N00°E 25.70'
Nail & KC Remon. tag SW side 14" Oak	S60°E 20.40'
Nail & KC Remon. tag W. side 14" Poplar (stump)	S15°E 39.05'
Nail & KC Remon. tag E. side 12" Oak	S15°W 5.90'

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:34
REG. OF DEEDS
Lucy [Signature]

10548

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN [Signature]



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 2/19/98