

FEB 08 1999

\$7.00  
\$2.00

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY  
(County)

Located in:

Corner Code #

- 1. Public Land Survey  
T 9N R 11W I-7
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling in Section  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous Property in Sec.  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

58 MAR -5 AM 8:34

REG. OF DEEDS

*David J. ...*

10549

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Jan. 14, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- I-7 1837 GLO Whitcomb Set Post
- 1964 Kent Co. Wits Mon. Box
- 1978 LCRC #1124 Merdzinski 1/2" Iron in Mon. Box
- 1982 LCRC #2517 Starr Set Kent County Monument in Mon. Box
- 1994 LCRC #7028 Byl Kent County Monument in Mon. Box

P.A. 345 1970 KENT COUNTY  
PEER APPROVED 2/19/98  
CHAIRMAN *Thomas C. Starr*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas C. Starr on 12-9-81 and was recorded per LCRC #2517.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-7 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Thomas C. Starr in place of the 1/2" Iron Pipe he found inside a Mon. Box. Said Iron Pipe checks with Kent Co. Wits. and LCRC #1124.

LCRC #2517	Nail & Remon. tag 26" Maple	South	36.93'	LCRC #7028	Nail & Remon. tag 30" Maple	S00°E	36.93'
	Nail & Remon. tag 30" Maple	S20°E	40.34'		Nail & Remon. tag 33" Maple	S20°E	40.34'
	Nail & Remon. tag 30" Maple	S45°E	53.80'		Nail & Remon. tag 33" Maple	S45°E	53.78'
	Nail & Remon. tag 26" Willow	N55°E	94.40'		Nail & Remon. tag Tri. 18" Willow	N55°E	94.29'
	Nail & Remon. tag 10" Sassafras	N25°E	62.53'		Nail & Remon. tag Tw. 15" Maple	N40°W	116.92'
	Nail & Remon. tag 20" Oak	N60°W	115.83'		Nail & Remon. tag P. Pole	N05°W	42.05'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-7 Standard Kent County Monument in Mon. Box
- Nail & KC Remon. tag W. side 30" Maple S00°E 36.93'
- Nail & KC Remon. tag E. side 33" Maple S20°E 40.34'
- Nail & KC Remon. tag NE side 33" Maple S45°E 53.78'
- Nail & KC Remon. tag SE side Tri. 18" Willow N55°E 94.23'
- Nail & KC Remon. tag SW side Tw. 15" Maple N40°W 116.92'
- Nail & KC Remon. tag W. side P. Pole N05°W 42.05'



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 2/19/98