

SURVEY & REMONUMENTATION

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SECTION _____

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>9</u> N	R <u>11</u> W	I-8
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 14, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-8	1837	GLO	Whitcomb	Set Post
	1969	Williams & Works		Found Bolt - Set 1 1/2" Iron Pipe
	1984	LCRC #3784	Byl	Set Kent County Monument
	1994	LCRC #7029	Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/19/98

CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 3-29-84 and was recorded per LCRC #3784.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-8 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by William R. Byl in place of the 1 1/2" Iron Pipe he found. Said Iron Pipe checks with Williams & Works information.

LCRC #3784		LCRC #7029	
Nail & Remon. tag 16" Beech	S85°W 75.11'	Nail & Remon. tag 16" Beech	S85°W 75.17'
Nail & Remon. tag 16" Hemlock	N00°E 102.85'	Nail & Remon. tag 16" Hemlock	N00°E 102.85'
Nail & Remon. tag 12" Tri. Maple	N65°E 103.08'	Nail & Remon. tag 12" Tri. Maple	N65°E 103.08'
Nail & Remon. tag 16" Twin Oak	S30°E 56.93	Nail & Remon. tag 18" Twin Oak	S30°E 56.99'
Nail & Remon. tag 16" Oak	S45°W 66.97'	Nail & Remon. tag 20" Oak	S45°W 67.01'

On E-W fence ± and tree row N.
The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-8 Standard Kent County Monument	
Nail & KC Remon. tag S. side 18" Beech	S85°W 75.17'
Nail & KC Remon. tag E. side 18" Hemlock	N00°E 102.85'
Nail & KC Remon. tag S. side 14" Tri. Maple	N65°E 103.08'
Nail & KC Remon. tag W. side 20" Twin Oak	S30°E 56.99'
Nail & KC Remon. tag W. side 22" Oak	S45°W 67.01'
C/L creek N. 50' ± and C/L creek E. 35' ±	



Signed by Kirk Breitels

Date 2/19/98

Surveyor's Michigan License No. 30077

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

Register of Deeds Stamp & File Number

10550

REG. OF DEEDS

Lucy Bond

98 MAR -5 AM 8:34

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD