

\$7.00
\$2.00

APR 08 1999

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REG. OF DEEDS

David J. Bond

98MAR-5 AM 8:34

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

For corners in

SECTION

KENT COUNTY
(County)

Located in:

Corner Code #

1. Public Land Survey		T <u>9</u> N R <u>11</u> W	I-10
		T ___ R ___	_____
		T ___ R ___	_____
		T ___ R ___	_____
2. Property Controlling in Section	S ___	T ___ R ___	_____
	S ___	T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___	T ___ R ___	_____
	S ___	T ___ R ___	_____

10552

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 9, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-10	1837	GLO	Whitcomb	Set Post
	1964	Kent Co. Wits		Mon Box
	1975	LCRC #897	Bonnema	1/4" Iron in Mon. Box
	1975	LCRC #899	Spicer	3/8" Iron in Mon. Box
	1982	LCRC #2521	Starr	Set Kent County Monument in Mon. Box
	1994	LCRC #7031	Byl	Kent County Monument in Mon. Box

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN Harold Stuber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas C. Starr on 1-5-82 and was recorded per LCRC #2521.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Thomas C. Starr in place of the 3/8" Solid Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC's #897 & #889.

LCRC #2521	Nail & Remon. tag 8" Pine	N20°W 47.64'	LCRC #7031	Nail & Remon. tag 6" Maple	N05°W 90.38'
	Nail & Remon. tag 2" Maple	N05°W 90.27'		Nail & Remon. tag 10" Oak	S70°W 45.45'
	Nail & Remon. tag 6" Oak	S70°W 45.60'		"+" mark of sta. 904+00 SB lane	N45°E 44.67'
	Nail & Remon. tag top guard post West	51.90'		W. edge of conc. SB lane (at rt. ang.) East	27.45'
	West edge conc. SB lane	East 27.45'			

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10	Standard Kent County Monument in Mon. Box	
	Nail & KC Remon. tag SE side 12" Oak	S70°W 45.42'
	"+" mark of sta. 904+00 S. Bd. Lane US-131	N45°E 44.67'
	West edge conc. S. bd. Lane US-131 (at rt. angle)	Easterly 27.45'
	East edge conc. parking lot (at rt. angle)	Westerly 53.07'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/19/98