

MAR 08 1998

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

\$7.00 SECTION  
\$2.00

For corners in

KENT COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T 9N R 11W	I-12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
98 MAR -5 AM 8:34  
REG. OF DEEDS  
*Lucy Bond*

10553

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-12	1837	GLO	Whitcomb	Set Post
		Kent Co. Wits		Leaded Stone
	1974	LCRC #682	Bonnema	"T" Iron
	1982	LCRC #3022	Starr	Set Kent County Monument
	1994	LCRC #7033	Byl	Kent County Monument

P.A. 345 1000 KENT COUNTY

PEER APPROVED 2/19/98  
CHAIRMAN Harry Kubicek

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas C. Starr on 8-2-82 and was recorded per LCRC #3022.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

I-12 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Thomas C. Starr in place of the 3/4" Iron Pipe over a "T" Iron he found. Both Irons checks with Kent Co. Wits. and LCRC #682.  
LCRC #3022

LCRC #3022		LCRC #7033	
Nail & Remon. tag 18" Oak	S10°W 5.37'	Nail & Remon. tag 24" Oak	S10°W 5.45'
Nail & Remon. tag 24" Oak West	41.69'	Nail & Remon. tag 28" Oak	N90°W 41.75'
Nail & Remon. tag 32" Oak	N30°W 61.63'	Nail & Remon. tag 36" Oak	N30°W 60.60'
Nail & Remon. tag 6" Maple	N20°E 40.94'	Nail & Remon. tag 8" Maple	N20°E 40.91'
Nail & Remon. tag 24" Oak	N60°E 52.83'	Nail & Remon. tag 27" Oak	N60°E 52.79'
Nail & Remon. tag 16" Oak	S50°E 18.93'	Nail & Remon. tag 20" Oak	S50°E 18.95'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12 Standard Kent County Monument	
Nail & KC Remon. tag W. side 24" Oak	S10°W 5.45'
Nail & KC Remon. tag N. side 28" Oak	N90°W 41.75'
Nail & KC Remon. tag SW side 36" Oak	N30°W 60.48'
Nail & KC Remon. tag W. side 8" Maple	N20°E 40.91'
Nail & KC Remon. tag S. side 27" Oak	N60°E 52.79'
Nail & KC Remon. tag SW side 20" Oak	S50°E 19.01'



Signed by *Lucy Bond*  
Surveyor's Michigan License No. 30077

Date 2/19/98