

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In: Corner Code #

- 1. Public Land Survey T9N R 11W I-13
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

95 MAR 20 AM 9:00

REG. OF DEEDS

W. J. [Signature]

9136

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 25, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/7/96
CHAIRMAN [Signature]

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-13	1837	GLO	Brookfield	Set Post
		Kent Co. Wit.		1" Iron-Mon. Box
	1976	LCRC #1011	Nederveld	3/4" Iron in Mon. Box
	1981	LCRC #1757	Merdzinski	Set Kent County Monument
	1994	LCRC #7034	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 1/19/81 and was recorded per LCRC #1757

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 3/4" Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wit. and LCRC #1011.

<u>LCRC #1757</u>		<u>LCRC #7034</u>
SE cor. frm. hse.	N05°W 118.15'	Nail/tag El. Serv. Pole N65°W 116.13'
SW cor. frm. hse.	N15°W 123.33'	Nail/tag El. Serv. Pole S65°W 124.27'
Nail/tag El. Pole	N65°W 116.13'	C/L Gas Marker Post S05°W 52.67'
Nail/tag El. Pole	S65°W 124.33'	Rerod N00°E 60.02'
C/L Gas Marker Post	S05°W 52.6'	Kent Co. Mon. S90°E 202.02'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 Standard Kent County Monument	
Nail & KC Remon. tag S. side Elec. Serv. Pole	N65°W 116.13'
Nail & KC Remon. tag N. side Elec. Serv. Pole	S65°W 124.27'
C/L Gas Main Marker Post	S05°W 52.67'
Rerod	N00°E 60.02'
Kent Co. Mon. (I-1, T8N, R11W)	S90°E 202.03'



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 3/2/96