

REMONUMENTATION

MAR 3 8 1999

\$7.00  
\$2.00

SECTION

### KENT COUNTY REMONUMENTATION

### LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
98 MAR -5 AM 8:34  
REG. OF DEEDS  
*Lucy Bond*

For corners in

KENT COUNTY  
(County)

Located In:	Corner Code #
T <u>10N</u> R <u>11W</u>	<u>J-1</u>
T <u>    </u> R <u>    </u>	<u>    </u>
T <u>    </u> R <u>    </u>	<u>    </u>
T <u>    </u> R <u>    </u>	<u>    </u>
S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

10554  
Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Jan. 7, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-1	1837	GLO	Whitcomb	Not Set
	1887	Williams & Works		Tree ?
	1966	MDSH		1/2" Pipe
	1968	Consumers Power		3 1/2" (?) Pipe
	1971	Williams & Works		Iron
	1977	LCRC #3322	Hay	1/2" Iron
	1995	LCRC #8537	Breitels	Set Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/19/98  
CHAIRMAN Harry Wuker

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Kirk Breitels on the Twp. line in place of the 1/2" Iron Pipe he found. Said Iron Pipe checks with Williams & Works, Consumers Power and LCRC #3322 LCRC #8537

Nail & KC Remon. tag top S. side E. culvert	S80°W	59.60'
Nail & KC Remon. tag top N. side E. culvert	N55°W	66.11'
Nail & KC Remon. tag E. side 24" Maple	N00°E	46.82'
Nail & KC Remon. tag NE side 12" Elm	S40°E	46.25'
Top angle point steel fence post	N70°E	76.30'
Kent Co. Mon. (J-13, T10N, R11W)	East	67.14'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1 Standard Kent County Monument		
Nail & KC Remon. tag top S. side E. culvert	S80°W	59.60'
Nail & KC Remon. tag top N. side E. culvert	N55°W	66.11'
Nail & KC Remon. tag E. side 24" Maple	N00°E	46.82'
Nail & KC Remon. tag NE side 12" Elm	S40°E	46.25'
Top angle point steel fence post	N70°E	76.30'
Kent Co. Mon. (J-13, T10N, R11W)	East	67.14'



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 2/19/98