

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
38 OCT -7 AM 10:15  
REG. OF DEEDS  
*Lucy Standa*

For corners in  
KENT COUNTY  
(County)

Located In:	Corner Code #
T 9N R 11W	J-4
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

10688

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on June 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-4	1837	GLO		Not Set
	1967	Williams & Works		Found Iron
	1983	LCRC #3263	Hay	Iron in Mon. Box
			MBT Pole SW 70.60'	MBT Pole NW 58.61' 10" Oak SSW 45.34'
	1992	Survey	Hackbardt	Mon. Box
			SE cor. blk. hse. N50°W 72.30' 14" Walnut	S30°E 122.55' C.P. N45°E 149.15'

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 7/23/98  
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-4 Found 1" Iron Pipe in Mon. Box. All witnesses per LCRC #3263 are gone.

Witnesses per Hackbardt: SE cor. blk. hse. N60°W 72.24'  
Nail W. side 14" Walnut S20°E 122.56'

Said Iron Pipe is 0.3' S. and less than 0.1' E. of intersection of 1/4 lines and has been used in surveys by Williams & Works, Hackbardt, Hay, W. Glaza.

The Iron Pipe in the Mon. Box is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-4	Set Standard Kent County Monument in Mon. Box in place of the 1" Iron Pipe.
	SE corner concrete block house N60°W 72.24'
	Nail & KC Remon. tag S. side 6" Poplar S85°W 60.22'
	Cut Nail W. side 14" Walnut S20°E 122.56'
	Nail & KC Remon. tag N. side Tw. 6" Elm S70°E 68.82'
	Nail & KC Remon. tag SE side P. Pole N55°E 119.61'



Signed by [Signature]  
Surveyor's Michigan License No. 30077

Date 9/25/98