

**SURVEY & REMONUMENTATION**

\$7.00  
\$2.00

MAR 08 1999

**KENT COUNTY REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY  
(County)

Located In:

Corner Code #

- |                                    |                            |       |
|------------------------------------|----------------------------|-------|
| 1. Public Land Survey              | T <u>9</u> N R <u>11</u> W | J-5   |
|                                    | T _____ R _____            | _____ |
|                                    | T _____ R _____            | _____ |
|                                    | T _____ R _____            | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____    | _____ |
|                                    | S _____ T _____ R _____    | _____ |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____    | _____ |
|                                    | S _____ T _____ R _____    | _____ |

REG. OF DEEDS

*David J. ...*

98 MAR -5 AM 8:34

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

10556

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breiteis, in a field survey on Jan. 19, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5									●			
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

- |     |      |               |           |                                      |
|-----|------|---------------|-----------|--------------------------------------|
| J-5 | 1837 | GLO           | Whitcomb  | Set Post                             |
|     | 1964 | Kent Co. Wits |           | 3/4" Iron                            |
|     | 1981 | LCRC #2069    | Nederveld | RR Spike in Mon. Box                 |
|     | 1982 | LCRC #2883    | Jonker    | Set Kent County Monument in Mon. Box |
|     | 1994 | LCRC #7036    | Byl       | Reset Kent County Monument           |

P.A. 345 1900 KENT COUNTY  
PEER APPROVED 2/19/98  
CHAIRMAN *Harry Stuber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 5-27-82 and was recorded per LCRC #2883.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

J-5 Found Kent Co. Mon. (Harrison) per wit. from above LCRC as reset by W.R. Byl in the same location as set in 1982 by Robert J. Jonker in place of the RR Spike he found in a Mon. Box. RR Spike checks Kent Co. Wits. and LCRC #2069.

- |            |                           |       |         |                            |       |         |
|------------|---------------------------|-------|---------|----------------------------|-------|---------|
| LCRC #2883 | Nail & Remon. tag P. Pole | N25°W | 80.17'  | "X" cut on C/L H/W         | N75°E | 98.05'  |
|            | Nail & Remon. tag P. Pole | S20°W | 99.38'  | "X" cut on C/L H/W         | S60°E | 104.01' |
|            | "X" on C/L H/W            | N75°E | 98.0'   | Nail & Remon. tag P. Pole  | S20°W | 98.97'  |
|            | "X" on C/L H/W            | S60°E | 103.94' | Nail & Remon. tag P. Pole  | N20°W | 156.93' |
|            | C/L bolt on S. end CMP    | S70°W | 114.7'  | Nail & Remon. tag 10" Pine | N50°E | 93.87'  |
|            | C/L bolt on N. end CMP    | N65°W | 111.72' |                            |       |         |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |                                   |                                       |       |         |
|-----------------------------------|---------------------------------------|-------|---------|
| J-5 Standard Kent County Monument | "X" cut on C/L headwall               | N75°E | 98.05'  |
|                                   | "X" cut on C/L headwall               | S60°E | 103.96' |
|                                   | Nail & KC Remon. tag E. side P. Pole  | S20°W | 98.84'  |
|                                   | Nail & KC Remon. tag W. side P. Pole  | N20°W | 156.93' |
|                                   | Nail & KC Remon. tag NW side 12" Pine | N50°E | 93.84'  |



Signed by *Kirk Breiteis*  
Surveyor's Michigan License No. 30077

Date 2/19/98