

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In: Corner Code #

- | | | | |
|------------------------------------|--------------|---------------|-------|
| 1. Public Land Survey | T <u>9</u> N | R <u>11</u> W | J-6 |
| | T ___ | R ___ | _____ |
| | T ___ | R ___ | _____ |
| | T ___ | R ___ | _____ |
| 2. Property Controlling in Section | S ___ | T ___ | R ___ |
| | S ___ | T ___ | R ___ |
| 3. Miscellaneous Property in Sec. | S ___ | T ___ | R ___ |
| | S ___ | T ___ | R ___ |

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 38 OCT -7 AM 10:15
 REG. OF DEEDS
David Board

10689

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk Breitels, in a field survey on Aug. 28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | |
|------|-----------|------------------|--|
| J-6 | 1837 | GLO | Not Set |
| | 1918 | Williams & Works | Point on N-S fence line |
| | 1952-56 | Williams & Works | Set Iron at Intersection of 1/4 lines (on fence to West) |
| | 1969 | Kent Co. Wits | Witnesses given |
| | | MBT NNW 47.37' | 4" Oak SSW 2.07' |
| | | | 24" Tw. Oak ESE 20.31' |
| | | | 16" Tw. Oak NNE 31.60' |
| 1973 | LCRC #383 | Spicer | 1" Solid Iron in Mon. Box |
| | | MBT S20°W 72.45' | 16" Oak N55°W 74.50' |
| | | | 12" Oak West 60.78' |
| | | | MBT N30°W 47.37' |

P.A. 345 1990 KENT COUNTY

PEER APPROVED 9/24/98

CHAIRMAN *Stan Huber*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- J-6 Found 1" Solid Iron in Mon. Box per the following remaining witnesses:
 C/L 18" Oak N55°W 74' ± C/L 16" Oak West 60.5' ± Nail in MBT Pole N30°W 47.37'
 On remains of old "stump" fence to West

Said 1" Solid Iron in Mon. Box is 16.1' N. & 0.3' W. of Intersection of 1/4 lines and has been used in surveys by Williams & Works, Hackbardt, Mich. State Hwy. Dept. (MDOT), Hay, Nederveld & Jonker. Did not find anything at the true intersection of 1/4 lines.

The 1" Solid Iron in Mon. Box is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-6 Set Standard Kent County Monument in place of the 1" Solid Iron and Mon. Box
- | | |
|--|--------------|
| Nail & KC Remon. tag SE side P. Pole | S30°W 46.83' |
| Nail & KC Remon. tag E. side Tel. Pole | N25°W 47.08' |
| Nail & KC Remon. tag S. side 16" Oak | N85°W 60.60' |
| Nail & KC Remon. tag E. side 10" Oak | N05°W 38.82' |
| Nail & KC Remon. tag E. side 14" Oak | S10°W 74.15' |
| C/L Edgerton Ave. (N-S) is East 50' ± | |



Signed by *Kirk Breitels*

Date 9/25/98

Surveyor's Michigan License No. 30077