

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

REG. OF DEEDS

98 OCT - 7 AM 10: 15

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

For corners in

KENT COUNTY  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 9N R 11W J-8
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

10690

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Aug. 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- J-8 1837 GLO Not Set
- Williams & Works No Information
- 1964 Kent Co. Wits Witnesses given - per MSHD
- 6" Ash ESE 10.7' 4" Elm Sse 2.5' 20" Maple ENE 22.06'
- 1991 LCRC #6200 Hackbardt 1" Pipe - 8.80' East of computed center - per MSHD
- 6" Ash S80°W 16.3' 7" DbL Willow S80°E 21.75' 1" Pipe West 8.80' Gd. Post N40°E 32.35'
- 1995-96 Surveys Exxel 3/4" Iron - per LCRC #6200

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 8/20/98  
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-8 Found 1" Iron Pipe per the following remaining witnesses:  
Nail in 6" Ash S80°W 16.3' Nail in 12" dbl. Willow S80°E 21.70' Nail in 12" Willow N40°W 14.81'  
1" Iron Pipe West 8.77' PK in top of Guard Rail Post N40°E 32.35'

Said 1" Iron Pipe per LCRC #6200 is 8.5' E. & 0.7' N. of Intersection of 1/4 lines and has been used by Hackbardt, Exxel and MSHD as the C 1/4 corner of Sec. 23.  
Other Iron Pipe found is 0.2' W. & 0.2' N. of Intersection of 1/4 lines. Do not know the origin of this Iron nor is there any documentation of its use in surveys.  
Based on extensive use of the 1" Iron Pipe per LCRC #6200, it is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-8 Set Standard Kent County Monument in place of the 1" Iron Pipe (per LCRC #6200).
- Nail & KC Remon. tag in top of guard rail post N40°E 32.32'
- West face of sign post S85°E 35.31'
- Nail & KC Remon. tag W. side Tw. 12" Maple S20°W 32.78'
- Nail & KC Remon. tag N. side 6" Ash S80°W 16.28'
- Nail & KC Remon. tag SW side 8" Ash N15°W 16.91'
- 1" Iron Pipe West 8.77'



Signed by [Signature]  
Surveyor's Michigan License No. 30077

Date 9/25/98