

MAR 08 1999

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T 9N R 11W	J-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
38 OCT -7 AM 10:15
REG. OF DEEDS
Lucy Bond

10674

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Sept. 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-9	1837	GLO	Whitcomb	Set Post
	1964	Kent Co. Wits		1" Iron
	1972	LCRC #293	VanKooten	1" Iron
	1982	LCRC #2524	Starr	Set Kent County Monument
	1994	LCRC #7038	Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/24/98
CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas C. Starr on 1-5-82 and was recorded per LCRC #2524.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9	Found BROKEN Kent Co. Monument (Harrison) per wits. from above LCRC as set by Thomas C. Starr in place of the 3/4" Iron over a 1/2 Iron he found. Both Irons check Kent Co. Wits. & LCRC #293. Removed and Reset Kent Co. Mon.
	LCRC #2524
	LCRC #7038
	Nail & Remon. tag MBT Pole N30°W 42.66'
	Nail & Remon. tag 8" Elm N70°W 66.12'
	Nail & Remon. tag 28" Oak S65°W 73.81'
	Nail & Remon. tag 30" Pine S50°W 55.88'
	Nail & Remon. tag MBT Pole S35°W 42.68'
	Nail & Remon. tag MBT Pole N10°E 55.20'
	Nail & Remon. tag 32" Oak S65°W 73.81'
	Nail & Remon. tag 32" Pine S50°W 55.88'
	Nail & Remon. tag Maple cluster N10°E 26.87'
	Nail & Remon. tag 12" Maple S45°E 71.49'
	Nail & Remon. tag 15" Cherry N60°W 64.53'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9	Standard Kent County Monument
	Nail & KC Remon. tag N. side 34" Oak S65°W 73.77'
	Nail & KC Remon. tag SE side 32" Pine S50°W 55.88'
	Nail & KC Remon. tag E. side Basswood cluster N10°E 26.80'
	Nail & KC Remon. tag NE side 14" Maple S45°E 71.46'
	Nail & KC Remon. tag S. side 18" Cherry N60°W 64.46'
	On C/L E-W asphalt road ±



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 9/24/98