

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey

T	9N	R	11W	K-2
T		R		
T		R		
T		R		
S		T		
S		T		
S		T		
S		T		

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-2	1837	GLO	Whitcomb	Set Post	1982 LCRC #2512	Starr	Set Kent County Monument
	1966	Kent Co. Wits		Iron in Mon. Box			In Mon. Box
	1971	LCRC #82	Spicer	1" Iron in Mon. Box	1994 LCRC #7041	Byl	Kent County Monument
	1974	LCRC #629	Spicer	1" Iron in Mon. Box			In Mon. Box
	1975	LCRC #822	McCloskey	3/4" Iron in Mon. Box			P.A. 345 1990 KENT COUNTY
	1979	LCRC #1291	Hackbardt	Iron in Mon. Box			PEER APPROVED 2/19/98

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas C. Starr on 1-5-82 and was recorded per LCRC #2512.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-2 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Thomas C. Starr in place of the 3/4" Iron Pipe over a 2nd 3/4" Iron Pipe he found inside a Mon. Box. Both Irons checks with all above.

LCRC #2512	Nail & Remon. tag P. Pole	N40°E	85.53'	LCRC #7041	Nail & Remon. tag P. Pole	N40°E	85.56'
	Nail & Remon. tag Tel. Pole	N10°W	98.02'		Nail & Remon. tag Tel. Pole	N10°W	98.04'
	Nail & Remon. tag 30" Oak	S60°W	63.97'		Nail & Remon. tag 33" Oak	S60°W	63.97'
	Nail & Remon. tag P. Pole	S40°W	57.51'		Nail & Remon. tag P. Pole	S40°W	57.49'
	Nail & Remon. tag 36" Oak	S20°W	83.64'		Nail & Remon. tag 36" Oak	S20°W	83.62'
	C/L 3" Maple	S45°E	91.4'				

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2 Standard Kent County Monument in Mon. Box	Nail & KC Remon. tag SE side P. Pole	N40°E	85.56'
	Nail & KC Remon. tag E. side Tel. Pole	N10°W	98.04'
	Nail & KC Remon. tag NW side 33" Oak	S60°W	63.97'
	Nail & KC Remon. tag SE side P. Pole	S40°W	57.49'
	Nail & KC Remon. tag E. side 36" Oak	S20°W	83.62'



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 2/19/98

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

98 MAR -5 AM 8:34

REG. OF DEEDS

10559

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2	●	1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												