

MAR 08 1998

KENT COUNTY REMONUMENTATION

\$7.00  
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
98 MAR -5 AM 8:34  
REG. OF DEEDS  
*W. J. Bond*

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T 9N R 11W K-9

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

10566

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-9	1837	GLO	Whitcomb	Set Post
	1956	Kent Co. Wits		Stone & Stake
	1977	LCRC #1028	Bonnema	3/4" Iron
	1977	LCRC #1093	VanKooten	3/4" Iron
	1981	LCRC #2555	Bueche	Set Kent County Monument
	1994	LCRC #7048	Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/19/98  
CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 12-21-81 and was recorded per LCRC #2555.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 1/4" Iron he found on top of a Stone. Said Iron over Stone checks with Kent Co. Wit. and LCRC's #1028 & #1093.

LCRC #2555		LCRC #7048	
Nail & Remon. tag 48" Oak	S35°W 24.95'	Nail & Remon. tag 48" Oak	S35°W 24.89'
Nail & Remon. tag P. Pole	S10°W 52.22'	Nail & Remon. tag P. Pole	S10°W 52.30'
Nail & Remon. tag 32" Oak	S70°E 65.55'	Nail & Remon. tag 36" Oak	S70°E 66.66'
Nail & Remon. tag 36" Maple	N70°E 65.80'	Nail & Remon. tag 40" Maple	N70°E 65.75'
NW corner house foundation	N50°E 139.06'	Nail & Remon. tag 30" Maple	N15°E 28.97'
		NW corner house foundation	N50°E 139.06'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9 Standard Kent County Monument			
Nail & KC Remon. tag E. side 48" Oak	S35°W	24.89'	
Nail & KC Remon. tag N. side 36" Oak	S70°E	66.66'	
Nail & KC Remon. tag S. side 40" Maple	N70°E	65.71'	
Nail & KC Remon. tag E. side 30" Maple	N15°E	28.97'	
NW corner house foundation	N50°E	139.06'	
Nail & KC Remon. tag E. side P. Pole	S10°W	51.73'	



Signed by

Kirk Breitels

Date

2/19/98

Surveyor's Michigan License No. 30077