

MAR 08 1999

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T. 9N R. 11W

K-10

T. R.

T. R.

T. R.

T. R.

2. Property Controlling in Section

S. T. R.

S. T. R.

3. Miscellaneous Property in Sec.

S. T. R.

S. T. R.

REG. OF DEEDS

Luigi Spada

98 MAR -5 AM 8:34

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

10567

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 5, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-10 1837	GLO	Whitcomb	Set Post
1973	LCRC #382	Spicer	"T" Iron
1979	LCRC #1289	Hackbardt	"T" Iron
1981	LCRC #2556	Bueche	Set Kent County Monument
1994	LCRC #7049	Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/19/98

CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 12-21-81 and was recorded per LCRC #2556.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the "T" Iron he found. Said "T" Iron checks with LCRC's #382 & #1289.

LCRC #2556	LCRC #7049
Nail & Remon. tag 14" Sassafras N90°W 19.88'	Nail & Remon. tag 16" Sassafras N90°W 19.90'
Nail & Remon. tag Tri. 8" Ash N50°W 12.67'	Nail & Remon. tag 16" Sassafras N20°E 16.90'
Nail & Remon. tag 12" Sassafras N20°E 16.80'	Nail & Remon. tag 16" Sassafras N70°E 13.49'
Nail & Remon. tag 14" Sassafras N70°E 13.47'	Nail & Remon. tag 14" Sassafras N30°W 10.49'
Stump row fence to North is 6' East	Nail & Remon. tag 6" Ash S20°W 29.44'
On stump row to East	Fence cor. to N & E is 10' N. and 10' E., on fence line W.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10 Standard Kent County Monument

Nail & KC Remon. tag S. side 16" Sassafras	N90°W 19.90'
Nail & KC Remon. tag W. side 16" Sassafras	N20°E 16.79'
Nail & KC Remon. tag N. side 16" Sassafras	N70°E 13.49'
Nail & KC Remon. tag E. side 14" Sassafras	N30°W 10.49'
Nail & KC Remon. tag W. side 6" Elm	S20°W 29.50'
Fence corner for fences North and East is 10' North ± and 10' East ±	
On fence line to West ±	



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 2/19/98