

\$7.00
\$2.00

KENT COUNTY REMONUMENTATION MAINTENANCE

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located in: Corner Code #

- 1. Public Land Survey T 9N R 11W K-13
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 98 DEC 23 AM 8:59
 REG. OF DEEDS
Lucy Spauld

11076

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Oct. 28, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	13		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- K-13 Kent County Monument, LCRC #9137, 3/2/96
- Nail & KC Remon. tag W. side P. Pole S65°W 63.17'
- Nail & KC Remon. tag N. side P. Pole S60°E 65.02'
- Nail & KC Remon. tag W. side Guy Pole N60°E 67.26'
- SE corner of brick house N30°W 91.35'
- NE face 8" vent pipe, 1' above ground S30°W 37.19'
- NE cor. Sec. 2-8-11 (Kent Co. Mon.) N90°E 109.09'

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 3/17/96
 CHAIRMAN *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 Found BROKEN Kent Co. Monument per above witnesses. Removed and reset Kent Co. Monument

SURVEY &
 REMONUMENTATION
 MAR 08 1999
 SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-13 Standard Kent County Monument
- Nail & KC Remon. tag N. side P. Pole S60°E 65.04'
- Nail & KC Remon. tag W. side Guy Pole N60°E 67.26'
- SE corner of brick house N30°W 91.35'
- NE face 8" vent pipe, 1' above ground S30°W 37.19'
- Nail & KC Remon. tag SE side new P. Pole S60°W 61.68'
- NE cor. Sec. 2-8-11 (Kent Co. Mon.) N90°E 109.09'



Signed by *[Signature]*
 Surveyor's Michigan License No. 30077

Date 12/15/98