

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T 9N R 11W

L-3

T R

T R

T R

T R

2. Property Controlling in Section

S

T R

S

T R

3. Miscellaneous Property in Sec.

S

T R

S

T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:34
REG. OF DEEDS
Lucy J. ...

10571

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Jan. 23, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- L-3 -1837 GLO Whitcomb Set Post
- Kent Co. Wits Leaded Stone
- 1975 LCRC #811 Bonnema "T" Iron
- 1979 LCRC #1291 Hackbardt "T" Iron
- 1980 LCRC #1488 Merdzinski Set Kent County Monument
- 1994 LCRC #7053 Byl Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN *Randy Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 12-1-80 and was recorded per LCRC #1488.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-3 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the "T" Iron he found. Said "T" Iron checks with Kent Co. Wits. and LCRC's #811 & #1291.

LCRC #1488	Nail & Remon. tag 18" Box Elder	N00°E 12.04'	LCRC #7053	Nail & Remon. tag 30" Stump	N00°E 12.17'
	Nail & Remon. tag 8" Elm	N50°E 35.92'		Nail & Remon. tag 12" Elm	N50°E 35.92'
	Nail & Remon. tag 6" Twin Elm	N90°E 67.87'		Nail & Remon. tag 10" Twin Elm	N90°E 67.95'
	Nail & Remon. tag 6" Elm	N70°E 66.11'		Nail & Remon. tag 12" Elm	N70°E 66.20'
	Nail & Remon. tag 20" Elm	S55°E 251.26'		Nail & Remon. tag 20" Stump	S55°E 251.20'

On Tree line N. and S. edge Tree line E.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-3 Standard Kent County Monument
- Cut Nail W. side 30" Stump N00°E 12.17'
- Nail & KC Remon. tag NW side 14" Elm N50°E 35.92'
- Nail & KC Remon. tag S. side 14" Twin Elm N90°E 67.91'
- Nail & KC Remon. tag NW side Twin 12" Elm N70°E 66.15'
- Nail & KC Remon. tag SW side 20" Stump S55°E 251.20'
- On S & W edge trees to N & E



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/19/98