

MAR 08 1999

\$7.00
\$2.00

SECTION

KENT COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:34
REG. OF DEEDS
Lucy Standa

For corners in

KENT COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>9</u> N R <u>11</u> W	<u>L-5</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

10572
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 9, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-5	1837	GLO	Whitcomb	Set Post
	1958	Williams & Works		Stone
		Kent Co. Wits		Witnesses given
	1975	LCRC #811	Bornema	Fd. Stone - set "T" Iron
	1978	LCRC #1158	Armeck	"T" Iron
	1980	LCRC #1457	Merdzinski	Set Kent Co. Mon.
	1994	LCRC #7054	Byl	Kent Co. Mon.

P.A. 345 1999 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN Harry Weber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 12-1-80 and was recorded per LCRC #1457.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-5 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the "T" Iron he found. Said "T" Iron checks with LCRC #811 and Williams & Works information and Kent Co. Wits.

LCRC #1487	LCRC #7054
Nail & Remon. tag S. side 12" Sassafras N90°E 54.16'	Nail & Remon. tag S. side 16" Sassafras N90°E 54.16'
Nail & Remon. tag W. side 4" Cherry S20°E 16.48'	Nail & Remon. tag W. side 10" Cherry S25°E 16.51'
Nail & Remon. tag NW side 6" Oak S35°W 45.15'	Nail & Remon. tag NW side 12" Oak S35°W 45.22'
Nail & Remon. tag E. side 6" Oak N15°W 8.78'	Nail & Remon. tag N. side 8" Oak S90°W 22.67'
SW corner pole barn frame N15°E 87.83'	SW corner pole barn frame N15°E 87.83'
Stone w/ "X" cut N 60 W 3.13' Tree line E-W-N	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5 Standard Kent County Monument	
Nail & KC Remon. tag S. side 18" Sassafras	N90°E 54.16'
Nail & KC Remon. tag W. side 12" Choke Cherry	S25°E 16.51'
Nail & KC Remon. tag NW side 16" Oak	S35°W 45.14'
Nail & KC Remon. tag N. side 10" Oak	S90°W 22.67'
SW corner Pole Barn Frame	N15°E 87.83'



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 2/19/98