

SURVEY & REMONUMENTATION

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|----------------------------|-------|
| 1. Public Land Survey | T <u>9</u> N R <u>11</u> W | L-6 |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
38 OCT -7 AM 10:15
REG. OF DEEDS
Lucy Stand

10695

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on June 25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-6 1837 GLO Not Set
1930-73 Williams & Works Iron
12" Elm ESE 15.0' 18" Elm SSE 16.75' 15" Pine SW 27.45' 15" Elm NW 13.0'
- 1956 Kent Co. Wits Iron - same witnesses as Williams & Works
- 1973 LCRC #540 Spicer Tall 1 1/2" Iron
14" Birch North 19.85' 10" Ash N50°W 32.5' Dbl. 12" Ash S50°E 43.45'

P.A. 345 1990 KENT COUNTY
PEER APPROVED 7/23/98
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-6 Found 2' tall 1 1/2" Iron Pipe per the following witnesses from above LCRC (older WW witnesses all gone)
Cut Nail E. side 20" Birch North 19.40'
Cut Nail NE side 15" Ash N50°W 32.35'

Said Iron Pipe is 14.8' S. and 2.5' W. of intersection of 1/4 lines and fits measurements of surveys by Williams & Works Medema & VanKooten and Hackbart.

The 2' tall 1 1/2" Iron Pipe is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-6 Set Standard Kent County Monument in place of the 2' tall 1 1/2" Iron Pipe - set Iron Pipe next to Monument
- Nail & KC Remon. tag NE side 12" Ash S45°E 63.26'
- Nail & KC Remon. tag E. side 20" Birch N00°E 19.25'
- Nail & KC Remon. tag NE side 15" Maple N50°W 32.14'
- Nail & KC Remon. tag NW side 15" Birch N60°E 27.20'
- NE corner foundation original house S10°W 141.61'
- NW corner foundation addition to hse. S45°W 143.85'



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 9/25/98