

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T 9N	R 11W	L-7
T	R	
T	R	
T	R	
T	R	

2. Property Controlling in Section

S	T	R	
S	T	R	
S	T	R	
S	T	R	

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORDS
98 MAR -5 AM 8:35
REG. OF DEEDS
Lucy Standa

10573

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kirk Breitels, in a field survey on Jan. 9, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-7	1837	GLO	Whitcomb	Set Post
	1946	Kent Co. Wits		Mon. Box
	1973	LCRC #540	Spicer	1 1/4" Iron in Mon. Box
	1981	LCRC #2558	Bueche	Set Kent County Monument in Mon. Box
	1994	LCRC #7055	Byl	Kent County Monument in Mon. Box

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 12-11-81 and was recorded per LCRC #2558.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 1 1/4" Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC #540.

LCRC #2558	LCRC #7055
"X" cut N. end conc. culv. N57°W 56.50'	"X" cut N. end conc. culv. N57°W 56.46'
"X" cut S. end conc. culv. S65°W 58.09'	"X" cut S. end conc. culv. S65°W 58.07'
SW corner house fndn. N40°E 102.95'	SW corner house fndn. N40°E 102.95'
Nail & Remon. tag 10" Pine S20°W 53.07'	Nail & Remon. tag 36" Oak N00°E 31.94'
C/L blktp. E-W is South 1.5' ±	Nail & Remon. tag P. Pole S75°W 84.12'
On East edge of Pines to South	Nail & Remon. tag 15" Pine S20°W 64.77'
	Nail & Remon. tag N75°W 84.05'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7 Standard Kent County Monument	
"X" cut on N. end conc. culvert	N57°W 56.46'
"X" cut on S. end conc. culvert	S65°W 58.01'
SW corner house foundation	N40°E 102.95'
Nail & KC Remon. tag W. side 38" Oak	N00°E 31.97'
Nail & KC Remon. tag N. side P. Pole	S75°W 84.12'
Nail & KC Remon. tag E. side 15" Pine	S20°W 64.77'
Nail & KC Remon. tag S. side Guy Pole	N75°W 84.05'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/19/98