

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 OCT - 7 AM 10: 15
REG. OF DEEDS
Luis J. Bond

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T 9N R 11W | L-8 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property In Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

10096
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Aug. 4, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | | |
|------|------------|-----------|------------------------|----------------------|----------------------|
| L-8 | 1837 | GLO | Williams & Works | Not Set | No Information |
| 1973 | LCRC #598 | Bonnema | 6" Cherry North 19.76' | 28" Oak ENE 71.20' | 16" Oak SW 51.66' |
| 1979 | LCRC #1290 | Hackhardt | 6" Cherry N10°W 19.48' | 28" Oak N45°E 71.20' | 16" Oak S30°W 51.60' |

P.A. 345 1990 KENT COUNTY
PEER APPROVED 8/20/98
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-8 Found 3/4" Iron Pipe per the following remaining witnesses:
Nail in 12" Cherry N00°W 19.51' Nail in 30" Oak N70°E 71.30'

Said 3/4" Iron Pipe is 1.8' S. & 0.8' E. of Intersection of 1/4 lines and has been used in surveys by Hackhardt, Exxel, Byl, and Roosien.

The 3/4" Iron Pipe is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-8 Set Standard Kent County Monument in place of the 3/4" Iron Pipe
- | | |
|---|--------------|
| Nail & KC Remon. tag E. side 12" Cherry | N00°W 19.51' |
| Nail & KC Remon. tag S. side 30" Oak | N70°E 71.30' |
| Nail & KC Remon. tag W. side 10" Poplar | S10°E 15.17' |
| Nail & KC Remon. tag N. side 12" Oak | S70°W 24.67' |



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 9/25/98