

CAR 0 8 1999

\$7.00
\$2.00

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T. 9N R. 11W	L-9
T. R.	
T. R.	
T. R.	
T. R.	
S. T. R.	
S. T. R.	
S. T. R.	
S. T. R.	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

98 MAR -5 AM 9:35

REG. OF DEEDS
For Record

10574

Register of Deeds Stamp & File Number

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Jan. 9, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-9	1837	GLO	Whitcomb	Set Post
	1961	Kent Co. Wits		3/4" Iron
	1971	LCRC #80	Chambers	1" Iron
	1981	LCRC #2559	Bueche	Set Kent County Monument
	1994	LCRC #7056	Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 12-21-81 and was recorded per LCRC #2559.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 1" Iron he found. Said Iron checks with Kent Co. Wits. and LCRC #80.

LCRC #2559	LCRC #7056		
Nail & Remon. tag 14" Oak	S55°W 31.68'	Nail & Remon. tag 24" Oak	S55°W 31.63'
Nail & Remon. tag P. Pole	S00°E 72.73'	Nail & Remon. tag P. Pole	S00°E 72.73'
Nail & Remon. tag 24" Maple	S80°E 135.40'	Nail & Remon. tag 30" Maple	S80°E 135.10'
Nail & Remon. tag 18" Sycamore	N55°E 60.03'	Nail & Remon. tag 24" Sycamore	N55°E 59.99'
SW corner house foundation	N32°E 97.65'	SW corner house foundation	N32°E 97.65'
Iron	N60°E 5.15'	C/L blktp. E-W is North 5.5' ±	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 Standard Kent County Monument	
Nail & KC Remon. tag NW side 24" Oak	S55°W 31.63'
Nail & KC Remon. tag W. side P. Pole	S00°E 72.76'
Nail & KC Remon. tag N. side 30" Oak	S80°E 135.10'
Nail & KC Remon. tag S. side 24" Sycamore	N55°E 59.99'
SW corner house foundation	N32°E 97.65'
C/L blktp. E-W is North 5.5' ±	



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 2/19/98