

7/2 SURVEY & REMONUMENTATION

MAR 08 1999

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

KENT COUNTY

(County)

Located in:

Corner Code #

1. Public Land Survey	T <u>9</u> N R <u>11</u> W	L-10
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
98 OCT -7 AM 10:15  
REG. OF DEEDS  
*Lucy Bond*

10697

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Aug. 3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

L-10 1837 GLO	Not Set
1928 Williams & Works	Fence Corner
1968-89 Williams & Works	Set/Used Iron on E-W 1/4 line per prev. surveys
1973 LCRC #382	Spicer "T" Iron
8" Cherry S15°W 7.95'	8" Oak N55°W 19.3'
16" Oak S85°E 7.25'	10" Maple N15°E 25.4'
1978 LCRC #1289	Iron 3.8' N. & 4.2' W.
8" Cherry S10°W 7.95'	Hackbardt 3/4" Iron
8" Oak N50°W 19.25'	10" Maple N20°E 25.25'

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 8/20/98  
CHAIRMAN *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-10 Found 3/4" Iron Pipe per the following remaining witnesses:  
Nail in 12" Cherry S10°W 8.00' Nail in 14" Oak N50°W 19.18' C/L Tri. 8"-18" Maple N20°E 25'  
Iron Pipe 3.8' N. & 4.2' W.

Said 3/4" Iron Pipe is 0.6' S. & 0.5' W. of Intersection of 1/4 lines and has been used in surveys by Williams & Works, Hackbardt, Chettleburgh and Nederveld.

The 3/4" Iron Pipe is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-10 Set Standard Kent County Monument in place of the 3/4" Iron Pipe	
Nail & KC Remon. tag E. side 12" Cherry	S10°W 8.00'
Nail & KC Remon. tag SW side 14" Oak	N50°W 19.18'
Nail & KC Remon. tag E. side Tri. 8"-18" Maples	N20°E 24.99'
Nail & KC Remon. tag N. side 30" Oak	S90°E 7.55'
Iron Pipe	N50°W 5.38'



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 9/25/98