

**SURVEY &
REMONUMENTATION**

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|--------------|---------------|-------------|
| 1. Public Land Survey | T <u>9</u> N | R <u>11</u> W | <u>L-13</u> |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

96 MAR 20 AM 9:00

REG. OF DEEDS
Lucy Bond
9138

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 25, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

L-13	1837	GLO	Brookfield	Set Post
		Kent Co. Wit.		Boat Spike
1981	LCRC #1837		Bonnema	PK Nail
1982	LCRC #2882		Jonker	Set Kent County Monument
1994	LCRC #7058		Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/7/96
CHAIRMAN *Harry Hubert*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 5/25/82 and was recorded per LCRC #2882.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the PK Nail he found. Said PK Nail checks with LCRC #1837 and old Williams & Works information.
LCRC #2882 & #7058

Nail & KC Remon. tag E. side guard post	S50°W	62.94'	Kent Co. Mon. (N 1/4 2-8-11)
Nail & KC Remon. tag E. side guard post	N55°W	53.18'	S90°E 35.04'
Nail & KC Remon. tag W. side guard post	N00°E	29.48'	
SW corner catch basin rim	N65°E	48.95'	
NW corner catch basin rim	S50°E	56.02'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 Standard Kent County Monument

Nail & KC Remon. tag E. side guard post	S50°W	62.94'
Nail & KC Remon. tag E. side guard post	N55°W	53.18'
Nail & KC Remon. tag W. side guard post	N00°E	29.48'
SW corner catch basin rim	N65°E	48.95'
NW corner catch basin rim	S50°E	56.02'
Kent Co. Mon. (N 1/4 2-8-11)	S90°E	35.04'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/6/96