

MAR 08 1999

KENT COUNTY REMONUMENTATION

\$7.00 SECTION
\$2.00

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T 9N R 11W	M-6
T R	common with
T 9N R 10W	A-6
T R	
S T R	
S T R	
S T R	
S T R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:35
REG. OF DEEDS
Luis S. Bond

10581

Register of Deeds Stamp & File Number

1. Public Land Survey

2. Property Controlling in Section
3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 4, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		0		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-6 1837 GLO	Brookfield	Set Post
1973 LCRC #540	Spicer	"T" Iron
1981 LCRC #2168	Jonker	Set Kent County Monument
1994 LCRC #7063	Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/19/98
CHAIRMAN Harry Hubert

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 10-1-81 and was recorded per LCRC #2168.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the "T" Iron he found. Said "T" Iron checks with LCRC #540.

LCRC #2168	LCRC #7063
Nail & Remon. tag 8" B. Elder N16°E 37.56'	Nail & Remon. tag 15" B. Elder N16°E 37.36'
Nail & Remon. tag 6" B. Elder N60°W 14.65'	Nail & Remon. tag 8" Cherry S60°W 32.81'
Nail & Remon. tag 6" Cherry S60°W 32.87'	Nail & Remon. tag 18" B. Elder S82°E 77.20'
Nail & Remon. tag 10" B. Elder S82°E 76.93'	Nail & Remon. tag 10" Cherry N60°W 7.25'
PK Nail in fence post S42°W 51.32'	PK Nail in fence post S42°W 51.37'

C/L creek is West 60' ±
The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 Standard Kent County Monument	
Nail & KC Remon. tag E. side 18" Box Elder	N16°E 37.36'
Nail & KC Remon. tag SE side 10" Cherry	S60°W 32.81'
Nail & KC Remon. tag N. side 20" Box Elder	S82°E 77.20'
Nail & KC Remon. tag S. side 12" Cherry	N60°W 7.25'
PK Nail in face of fence post (leaning)	S42°W 51.60'
C/L creek is West 60' ±	
C/L Porter Hollow Rd. is North 406' ±	



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/19/98