

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
38 OCT -7 AM 10:15
REG. OF DEEDS
Lucy Bond

10676

Register of Deeds Stamp & File Number

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T 9N R 11W	M-10
T 9N R 10W	A-10
T R	
T R	
S T R	
S T R	
S T R	
S T R	

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Sept. 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-10 1837	GLO	Brookfield	Set Post
	Kent Co. Wits		PK in pavement
1976	LCRC #928	McCloskey	Monument
1981	LCRC #1986	Jonker	Set Kent County Monument in Mon. Box
1994	LCRC #7067	Byl	Kent County Monument in Mon. Box

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/24/98
CHAIRMAN *Harry Hubert*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 8-26-81 and was recorded per LCRC #1986.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-10 Found PK Nail at same location as Kent Co. Mon. per witnesses from above LCRC as set by Robert J. Jonker in place of the 1/2" Copper Conduit he found inside a Mon. Box. Said Copper Conduit checks LCRC's #928 & 1986.
LCRC #1986

Nail & Remon. tag 26" Box Elder	S38°E 120.5'	Nail & Remon. tag 33" Box Elder	S38°E 120.40'
Nail & Remon. tag 14" Maple	S88°E 69.16'	Nail & Remon. tag 18" Maple	S88°E 69.16'
Nail & Remon. tag 9" Locust	N75°W 40.9'	Nail & Remon. tag 12" Locust	N75°W 40.91'
Nail & Remon. tag 6" Oak	N43°W 41.05'	Nail & Remon. tag 10" Oak	N43°W 41.20'

C/L traveled way, Easterly 6' ±

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10 Standard Kent County Monument		
Nail & KC Remon. tag W. side P. Pole	S20°W	150.96'
Nail & KC Remon. tag S. side P. Pole	S90°W	58.78'
Nail & KC Remon. tag SW side 33" stump	S38°E	120.32'
Nail & KC Remon. tag S. side 18" stump	S88°E	69.12'
Nail & KC Remon. tag E. side P. Pole	N25°W	134.71'
Concrete Monument - West		60.00'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 9/24/98