

MAR 08 1999

\$7.00
\$2.00

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T ___ R ___
T ___ R ___
T ___ R ___
T ___ R ___

2. Property Controlling
in Section

S 36 T 9N R 11W Wit. Mon. on
S ___ T ___ R ___ N-S 1/4 line

3. Miscellaneous
Property in Sec.

S ___ T ___ R ___
S ___ T ___ R ___

REG. OF DEEDS

Lucy Bond

98 NOV 16 AM 8:00

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

other code # 3

10923

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kirk Breitels, in a field survey on Nov. 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO Whitcomb Not Set

P.A. 345 1990 KENT COUNTY

PEER APPROVED 10/22/98

CHAIRMAN *Harry Hubert*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Established 1/8 corner between the North 1/4 corner and the Central 1/4 corner recorded in LCRC # 10921.

This location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the Witness Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Kent County Witness Monument at the 1/8 corner between the North 1/4 cor. and the computed Central 1/4 cor.

Rerod - property corner S90°E 70.20'
Nail & KC Remon. tag W. side 6" Oak S00°W 33.81'
Nail & KC Remon. tag N. side 12" Oak S70°W 40.49'
Nail & KC Remon. tag W. side 12" Poplar N20°E 24.42'
Concrete plat monument S60°W 2.31'

Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 11/12/98

