

SURVEY & REMONUMENTATION

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located in:

Corner Code #

- | | | |
|------------------------------------|--------------------------|-------|
| 1. Public Land Survey | T <u>9N</u> R <u>12W</u> | A-2 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:28
REG. OF DEEDS
Lucy J. Bond

10422

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Jan. 20, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

- A. Description of original monument and accessories and/or subsequent restoration:
- | | | | | |
|-----|------|---------------|--------------|--------------------------|
| A-2 | 1837 | GLO | Brookfield | Set Post |
| | 1943 | Kent Co. Wits | | Iron & Stones |
| | 1984 | LCRC #3806 | Chettleburgh | Set Kent County Monument |
| | 1991 | LCRC #6116 | Byl | Kent County Monument |

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN Harry Tubert

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas M. Chettleburgh on 4-30-84 and was recorded per LCRC #3806.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- A-2 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Thomas M. Chettleburgh over top of the Iron Pipe (36" deep) he found. Said Iron Pipe checks with Williams & Works information. Kent Co. Wits. gone.
- | | |
|---|---|
| LCRC #3806 | LCRC #6116 |
| Nail & Remon. tag 27" Willow N38°E 71.46' | Nail & Remon. tag 30" Willow N38°E 71.34' |
| Nail & Remon. tag 32" Willow N67°E 68.40' | Nail & Remon. tag 36" Willow N67°E 68.70' |
| Nail & Remon. tag 13" Elm S70°E 55.01' | Nail & Remon. tag 13" Elm S70°E 55.01' |
| Nail & Remon. tag 7" Elm S90°W 80.48' | Nail & Remon. tag 16" Pine S30°E 147.16' |
| Nail & Remon. tag 8" Elm S90°W 83.83' | Iron Pipe in Mon. Box S14°W 2.22' |
| Iron pipe in Mon. Box S14°W 2.22' | Steel bar & cap (All-Points) S45°E 46.61' |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- A-2 Standard Kent County Monument
- | | | |
|---|-------|---------|
| Nail & KC Remon. tag W. side 40" Willow | N38°E | 71.26' |
| Nail & KC Remon. tag SE side 42" Willow | N67°E | 68.42' |
| Nail & KC Remon. tag W. side 18" Pine | S30°E | 147.12' |
| Nail & KC Remon. tag N. side P. Pole | S90°W | 54.06' |
| Steel bar & cap (All-Points) | S45°E | 46.61' |
| Iron pipe in Mon. Box | S14°W | 2.22' |



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 2/19/98