

SURVEY & REMONUMENTATION

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$7.00
\$2.00

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:28
REG. OF DEEDS
Luci Standa

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T 9N R 12W	A-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

10423

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 20, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

A-5	1837	GLO	Brookfield	Set Post
	1961	T & H Assoc.		Plow Point
	1968	Williams & Works		Plow Point
	1968	Consumers Power		Plow Point
	1984	LCRC #3939	Kolehouse	Found Ottawa County Monument in Mon. Box (set by Ottawa Co. Surveyor)
	1991	LCRC #6119	Byl	Ottawa County Monument in Mon. Box

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN Randy Kolehouse

The position of this corner (Ottawa County Monument) was previously approved by the Kent County Remonumentation Peer Group, as confirmed by Randy J. Kolehouse on 9-29-84 and was recorded per LCRC #3939.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-5 Found Ottawa County Monument in Mon. Box per witnesses from above LCRC as confirmed by Randy J. Kolehouse. Said Ottawa County Monument checks with T & H Assoc., Williams & Works and Consumers Power information.

LCRC #3939		LCRC #6119
Nail & Remon. tag P. Pole	N60°E 100.18'	Nail & Remon. tag P. Pole N60°E 100.18'
Nail & Remon. tag P. Pole	S60°E 75.96'	Nail & Remon. tag P. Pole S60°E 74.99'
Nail & Remon. tag 16" Apple	N60°W 75.92'	Nail & Remon. tag 24" Elm S20°W 124.70'
Nail & Remon. tag Twin 6" Pine	S35°W 71.13'	Nail & Remon. tag 18" Apple N40°W 72.27'
At C/L "X" Kenowa Ave. and 14 Mile Road		SW corner fnd. Hse. #4773 N50°E 148.95'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5 Ottawa Kent County Monument in Mon. Box
Nail & KC Remon. tag N. side P. Pole N60°E 100.18'
Nail & KC Remon. tag S. side P. Pole S60°E 74.99'
Nail & KC Remon. tag E. side 28" Elm S20°W 124.88'
Nail & KC Remon. tag E. side 20" Apple N40°W 72.27'
SW corner foundation House #4773 N50°E 148.95'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/19/98