

**SURVEY & REMONUMENTATION**

**\$7.00**  
**\$2.00**

MAR 08 1999

**KENT COUNTY REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T 9N R 12W

A-6

T     R    

T     R    

T     R    

2. Property Controlling in Section

S    

T     R    

3. Miscellaneous Property in Sec.

S    

T     R    

S    

T     R    

4. Lot No.           , Recorded Plat           

5. Private Claims           

REG. OF DEEDS

*[Signature]*

98 MAR -5 AM 8:28

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

10424

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kirk Breiteis, in a field survey on Jan. 20, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-6 1837 GLO Brookfield Set Post
- 1944 Kent Co. Wits 1 1/2" Pipe
- 1954 Williams & Works Iron
- 1984 LCRC #3936 Kolehuse Set Kent County Monument
- 1991 LCRC #6120 Byl Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/19/98

CHAIRMAN *[Signature]*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehuse on 9-29-84 and was recorded per LCRC #3936.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6 Found Kent County Monument (Harrison) in a Mon. Box per witnesses from above LCRC as set by Randy J. Kolehuse in place of the 1/2" Re-bar he found in a newly paved road. Re-bar checks with Kent Co. Wits. and Williams & Works. LCRC #3936

Nail & Remon. tag P. Pole N85°E 54.65'  
Nail & Remon. tag 3" Elm N80°W 140.60'  
C/L Kenowa Ave. blacktop is East 0.5'

LCRC #6120  
Nail & Remon. tag P. Pole N85°E 54.62'  
Nail & Remon. tag 6" Elm N80°W 140.35'  
Meas. S. to A-7: 2651.15'  
Meas. N. to A-5: 2642.04'  
Meas. Angle N-E-S: 180°11'45"

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-6 Standard Kent County Monument in Mon. Box
- Nail & KC Remon. tag N. side P. Pole N85°E 54.60'
- Nail & KC Remon. tag W. side P. Pole N10°E 295.75'
- Concrete Monument (2<sup>nd</sup> Order GPS Point) S30°E 87.52'
- EDM Meas. S. to A-7: 2651.16'
- EDM Meas. N. to A-5: 2642.06'
- Meas. Angle N-E-S: 180°12'05" (single)



Signed by *[Signature]*  
Surveyor's Michigan License No. 30077

Date 2/19/98