

**SURVEY & REMONUMENTATION**

**\$7.00**  
**\$2.00**

MAR 08 1999

**KENT COUNTY REMONUMENTATION**

**SECTION LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

KENT COUNTY

(County)

Located in:

Corner Code #

1. Public Land Survey	T <u>9N</u>	R <u>12W</u>	A-8
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

REG. OF DEEDS

*Lucy St. Grand*

99 MAR -5 AM 8:28

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

10426

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 12, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

A-8	1837	GLO	Brookfield	Set Post
	1963	Kent Co. Wits		2" Iron
	1976	LCRC #952	Bonnema	RR Spike
	1982	LCRC #3194	Bonnema	Set Kent County Monument in Mon. Box
	1991	LCRC #6122	Byl	Kent County Monument in Mon. Box

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/19/98  
CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Douglas W. Bonnema on 12-7-82 and was recorded per LCRC #3194.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

A-8 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Douglas W. Bonnema in place of the 18" "L" Iron he found inside a Mon.Box. Said "L" Iron checks with LCRC #952.

LCRC #3194	"X" in culvert (N. end)	N35°E 45.03'	LCRC #6122	"X" in culvert (N. end)	N35°E 45.09'
	"X" in culvert (S. end)	N44°W 37.21'		"X" in culvert (S. end)	N44°W 37.10'
	Nail & Remon. tag 14" Apple	S55°E 52.77'		Nail & Remon. tag P. Pole	S29°E 126.20'
	Capped Exxel re-rod	S11°W 52.67'		Nail & Remon. tag 14" Apple	S55°E 52.22'
	Nail & Remon. tag P. Pole	S29°E 126.09'			

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A-8 Standard Kent County Monument in Mon. Box	"X" in culvert (North end)	N35°E 45.09'
	"X" in culvert (South end)	N44°W 37.10'
	Nail & KC Remon. tag SW side P. Pole	S29°E 126.20'
	Nail & KC Remon. tag SW side 16" Apple	S55°E 52.22'



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 2/19/98