

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

\$7.00
\$2.00

MAR 08 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

<u>KENT COUNTY</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>12W</u>	<u>A-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

98 MAR -5 AM 8:28

REG. OF DEEDS

10429

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 12, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-11 1837 GLO	Brookfield	Set Post
1976 LCRC #952	Bonnema	RR Spike in Mon. Box
1982 LCRC #3197	Bonnema	Set Kent County Monument in Mon. Box
1991 LCRC #6125	Byl	Kent County Monument in Mon. Box

P.A. 345 1900 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Douglas W. Bonnema on 12-8-82 and was recorded per LCRC #3197.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-11 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Douglas W. Bonnema in place of the RR Spike he found inside a Mon. Box. Said RR Spike checks with LCRC #952.

LCRC #3197	LCRC #6125
Nail & Remon. tag 12" Apple S45°E 62.34'	Nail & Remon. tag 12" Maple N31°E 89.74'
Nail & Remon. tag 12" Maple N31°E 89.81'	Nail & Remon. tag 30" Maple N19°W 77.08'
Nail & Remon. tag 26" Maple N19°W 77.15'	Nail & Remon. tag 30" Maple N63°W 83.12'
Nail & Remon. tag 26" Maple N63°W 83.12'	Nail & Remon. tag 5" Apple S42°W 63.54'
Nail & Remon. tag 5" Maple S42°W 63.42'	
2'S. & 2' W. of C/L "X" roads N-S-W	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11 Standard Kent County Monument in Mon. Box

Nail & KC Remon. tag SE side 15" Maple	N31°E	89.74'
Nail & KC Remon. tag E. side 33" Maple	N19°W	76.98'
Nail & KC Remon. tag S. side 33" Maple	N63°W	83.03'
Nail & KC Remon. tag NW side 8" Apple	S42°W	63.54'



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 2/19/98