

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

90 JUL 14 AM 9:54

W. J. Bond
REG. OF DEEDS

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)	Located In:	Corner Code #
1. Public Land Survey	T ^{9N} R ^{12W}	B-1
	T_____ R_____	_____
	T_____ R_____	_____
	T_____ R_____	_____
2. Property Controlling in Section	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____
3. Miscellaneous Property in Sec.	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____

10653
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on May 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-1 1837 GLO Whitcomb Not Set
1992 LCRC #6600 Bueche Set Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/25/98
CHAIRMAN Harold Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 10-12-92 and was recorded per LCRC #6600.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1 Found Kent County Monument (Harrison) per witnesses from above LCRC as set on Twp. Line by John C. Bueche. LCRC #6600

- Nail & Remon. tag S. side 20" Walnut N75°E 144.51'
- Nail & Remon. tag E. side 10" Walnut N35°E 33.06'
- Nail & Remon. tag W. side 18" Walnut N05°E 102.56'
- Nail & Remon. tag E. side T. Pole N25°W 243.13'
- Nail & Remon. tag E. side T. Pole S70°W 213.39'
- K.C. Mon. at S 1/4 31-10-12 East 15.18'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1 Standard Kent County Monument
Nail & KC Remon. tag S. side 22" Walnut N75°E 144.51'
Nail & KC Remon. tag E. side 12" Walnut N35°E 33.06'
Nail & KC Remon. tag W. side 20" Walnut N05°E 102.56'
Nail & KC Remon. tag E. side P. Pole N25°W 243.13'
Nail & KC Remon. tag E. side P. Pole S70°W 213.39'
Nail & KC Remon. tag N. side P. Pole S75°E 197.90'
Kent Co. Mon. (B-13, T10N, R12W) East 15.21'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 6/25/98