

\$7.00
\$2.00
MAR 08 1999
SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
38 NOV 16 AM 8:00
REG. OF DEEDS
W. J. Sand

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T 9N R 12W	B-8
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.

10925

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on July 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-8 1837	GLO	Not Set
1903	Williams & Works	Set Stake & Stone on line and 1/2 way between North and South 1/4 corners
	Kent Co. Wits	No information

P.A. 345 1990 KENT COUNTY
PEER APPROVED 7/23/98
CHAIRMAN Harry Huber

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-8 Did not find anything at corner. Established Intersection of 1/4 lines and found to be on N-S fence line. Fence to West is 20' South (fits 1903 Williams & Works location ±). No occupation to West.

No recent or previously recorded information in this section to compare with.

The Intersection of 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-8 Set Standard Kent County Monument at Intersection of 1/4 lines.

Nail & KC Remon. tag N. side 15" Elm	S80°E	126.21'
Nail & KC Remon. tag NE side 6" Elm	S45°E	31.40'
Nail & KC Remon. tag E. side 6" Ash	N00°E	11.45'
Nail & KC Remon. tag S. side 6" Apple	N80°E	25.43'
Nail & KC Remon. tag NW side 6" Apple	N40°E	38.11'

On N-S fence line ±
Fence to West is 20' South ±



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 11/12/98