

LAND SURVEY & REMONUMENTATION

MAR 08 1999

KENT COUNTY REMONUMENTATION

\$7.00  
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY  
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 9N R 12W C-2
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
98 MAR -5 AM 8:28  
REG. OF DEEDS  
*Lucy Hand*

10434

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	●	5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Kirk Breitels, in a field survey on Jan. 20, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- |     |      |               |            |                                        |
|-----|------|---------------|------------|----------------------------------------|
| C-2 | 1837 | GLO           | Whitcomb   | Set Post                               |
|     |      | Kent Co. Wits |            | 3/4" Iron                              |
|     | 1974 | LCRC #752     | Spicer     | 1 1/2" Iron in Mon. Box                |
|     | 1982 | LCRC #2950    | Merdzinski | Set Kent County Monument in Mon. Box   |
|     | 1991 | LCRC #6133    | Byl        | Reset Kent County Monument in Mon. Box |

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/19/98  
CHAIRMAN *Harry Stuber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 6-28-82 and was recorded per LCRC #2950.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- C-2 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by William R. Byl at the same location as set in 1982 by John A. Merdzinski in place of the 1 1/2" Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC #752.

LCRC #2950	Nail & Remon. tag 12" Pear	S85°E	25.51'	LCRC #7133	Nail & Remon. tag P. Pole	S70°W	52.18'
	Nail & Remon. tag 12" Pear	S40°E	55.80'		Nail & Remon. tag 10" Elm	S35°E	40.34'
	Nail & Remon. tag 14" Apple	S50°W	71.38'		Nail & Remon. tag P. Pole	N10°W	207.51'
	Nail & Remon. tag P. Pole	S70°W	52.20'		Cut "X" top N. end conc. culv.	N60°W	28.07'

C/L N-S road is W. 1' & is on C/L trail W.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-2 Standard Kent County Monument in Mon. Box
- |                                       |       |         |
|---------------------------------------|-------|---------|
| Nail & KC Remon. tag N. side P. Pole  | S70°W | 52.24'  |
| Nail & KC Remon. tag top of 12" Stump | S35°E | 40.56'  |
| Nail & KC Remon. tag E. side P. Pole  | N10°W | 207.51' |
| "X" cut on top N. end conc. culvert   | N60°W | 28.07'  |



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 2/19/98