

SURVEY & REMONUMENTATION

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$7.00
\$2.00

For corners in

KENT COUNTY
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 9N R 12W C-5
 T R
 T R
 T R
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 20, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-5 1837 GLO Whitcomb Set Post
- 1963 Kent Co. Wits 2" Iron
- 1979 LCRC #1257 Bonnema 1/2" Iron in Mon. Box
- 1980 LCRC #1339 Merdzinski 5/8" Iron in Mon. Box
- 1982 LCRC #2969 Merdzinski Set Kent County Monument in Mon. Box
- 1991 LCRC #6136 Byl Reset Kent County Monument in Mon. Box

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 2/19/98
 CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 7-1-82 and was recorded per LCRC #2969.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-5 Found Kent County Monument (Harrison) in a Mon. Box per witnesses from above LCRC as set by William R. Byl at the same location as set in 1982 by John Merdzinski in place of the 5/8" Iron over a 2" Iron he found inside a Mon. Box. Both Irons check with Kent Co. Wits. and LCRC's #1257 & #1339.

LCRC #2969	Nail & Remon. tag P. Pole N30°W 96.55'	LCRC #6136	Nail & Remon. tag P. Pole N30°W 96.52'
	Nail & Remon. tag 20" Maple S85°W 193.50'		Nail & Remon. tag 24" Maple S15°E 121.67'
	Nail & Remon. tag 18" Maple S15°E 122.00'		NW cor. MBT Box S40°E 74.81'
	NW corner MBT Box S40°E 74.75'		Nail & Remon. tag P. Pole S80°E 154.70'
	Nail & Remon. tag P. Pole S80°E 154.75'		PK Nail curb joint N50°E 33.33' & S55°W 43.23'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-5 Standard Kent County Monument in Mon. Box
- Nail & KC Remon. tag W. side P. Pole N30°W 96.59'
- Nail & KC Remon. tag W. side 28" Maple S15°E 121.67'
- NW corner Tele. Box S40°E 74.81'
- Nail & KC Remon. tag N. side P. Pole S80°E 154.75'
- PK Nail in curb joint N50°E 33.71'
- PK Nail & Remon. tag in curb joint S55°W 43.21'



Signed by Kirk Breitels
 Surveyor's Michigan License No. 30077

Date 2/19/98

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD

98 MAR -5 AM 8:28

REG. OF DEEDS

Luis Standa

10436
 Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5		•										
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												