

SURVEY & REMONUMENTATION

MAR 08 1999

KENT COUNTY REMONUMENTATION

\$7.00
\$2.00

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>12W</u>	<u>C-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 98 MAR -5 AM 8:28
 REG. OF DEEDS
Luis Standa

10438

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 13, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-7	1837	GLO	Whitcomb	Set Post
			Kent Co. Wits	Concrete Monument
	1972	LCRC #209	Bonnema	3/4" Solid Rod in Mon. Box
	1982	LCRC #2622	Nederveld	Set Kent County Monument in Mon. Box
	1991	LCRC #6138	Byl	Kent County Monument in Mon. Box

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 2/19/98
 CHAIRMAN *Harry Faber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Gordon D. Nederveld on 1-25-82 and was recorded per LCRC #2622.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-7 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Gordon D. Nederveld in place of the Solid Rod he found inside a Mon. Box. Said Solid Rod checks with Kent Co. Wits. and LCRC #209.

LCRC #2622		LCRC #6138
Nail & Remon. tag P. Pole	S20°E 104.23'	Nail & Remon. tag P. Pole S20°E 104.19'
Nail & Remon. tag P. Pole	S46°E 46.15'	Nail & Remon. tag P. Pole S46°E 46.15'
Nail & Remon. tag T. Pole	N60°E 53.07'	Nail & Remon. tag Guy Pole N56°W 54.21'
Nail & Remon. tag Guy Pole	N56°W 54.18'	Nail & Remon. tag P. Pole N65°E 102.53'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7 Standard Kent County Monument in Mon. Box
Nail & KC Remon. tag W. side P. Pole S20°E 104.19'
Nail & KC Remon. tag SW side P. Pole S46°E 46.11'
Nail & KC Remon. tag NE side Guy Pole N56°W 54.21'
Nail & KC Remon. tag NW side P. Pole N65°E 102.53'



Signed by *Kirk Breitels*
 Surveyor's Michigan License No. 30077

Date 2/19/98