

SURVEY & REMONUMENTATION

MAR 08 1999

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$7.00
\$2.00

SECTION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 9:28
REG. OF DEEDS
W. J. Huber

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|----------------------------|-------|
| 1. Public Land Survey | T <u>9</u> N R <u>12</u> W | C-8 |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

10439

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 13, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | |
|-----|------|---------------|-----------|--------------------------------------|
| C-8 | 1837 | GLO | Whitcomb | Set Post |
| | 1940 | Kent Co. Wits | | Concrete Monument |
| | 1983 | LCRC #3451 | Jonker | 3/4" Iron in Mon. Box |
| | 1983 | LCRC #3632 | Kolehouse | Set Kent County Monument in Mon. Box |
| | 1991 | LCRC #6139 | Byl | Kent County Monument in Mon. Box |

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/19/98
CHAIRMAN W. J. Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 11-26-83 and was recorded per LCRC #3632.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-8 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the 1" Iron he found over the remains of a Concrete Monument. Both Iron & Conc. Mon. check with Kent Co. Wits. and LCRC #3451.

- | | | | | |
|------------|--------------------------------|---------------|--------------------------------|---------------|
| LCRC #3632 | Nail & Remon. tag P. Pole | N85°W 61.61' | Nail & Remon. tag P. Pole | N85°W 61.68' |
| | Nail & Remon. tag 40" Maple | N15°E 200.70' | Top C/L N. end 12" conc. culv. | N60°W 41.45' |
| | Nail & Remon. tag 4" Cherry | N25°E 99.50' | SE face of yard light post | N30°W 129.35' |
| | Top C/L N. end 12" conc. culv. | N60°W 41.45' | C/L top of MBT Ped. #10412 | N25°E 141.90' |
| | C/L pavement is East 1.3' | | | |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | | |
|-----|---|---------------|--|
| C-8 | Standard Kent County Monument in Mon. Box | | |
| | Nail & KC Remon. tag N. side P. Pole | N85°W 61.68' | |
| | Top C/L N. end 12" conc. driveway culvert | N60°W 41.45' | |
| | SE face of yard light post | N30°W 129.35' | |
| | C/L top of Tele. Pedestal #10412 | N25°E 141.90' | |



Signed by

Kirk Breitels

Date

2/19/98

Surveyor's Michigan License No.

30077